



FASTENERS APPROX. 8" O.C. (203mm)

FIRST MEMBRANE FLASHING PLY

PRIMED MASONRY SUBSTRATE. ON WOOD FASTEN SOPREMA APPROVED BASE SHEET 8" O.C. (203mm) IN GRID PATTERN AND AT SIDE LAPS.

SOPRAFIX PLATFORM MEMBRANE, FASTENED PER CURB AND PERIMETER LAYOUT DETAILS.

WOOD NAILERS INSTALLED WITH BOND BREAKERS AND FASTENED AS SPECIFIED OR REQUIRED BY CODE OR INDUSTRY STANDARDS TO RESIST DESIGN LOADS AND CORROSION OF STEEL DECKING, FASTENERS AND METAL EDGING.

COVERBOARD INSULATION (IF REQUIRED)

THERMAL INSULATION (IF REQUIRED)

ROOF DECK

UNIT MOUNTING CURB

FASTENER AND SEALING WASHERS SPACED AS SPECIFIED

REMOVABLE METAL COUNTERFLASHING EXTENDER PIECE

CAP MEMBRANE FLASHING PLY

UNILAY MEMBRANE PLY EMBED GRANULES IN FLASHING AREA.

NOTES:

1. DETAIL TO BE USED IN CONJUNCTION WITH SOPREMA GENERAL REQUIREMENTS AND APPROVED DETAILS.
2. CONSTRUCT OTHER ROOF COMPONENTS ACCORDING TO PROJECT SPECIFICATIONS AND CURRENT RECOMMENDATIONS FROM FMA, SMACNA AND NRCA.
3. SOPREMA FLASHING ADHESIVE, MASTIC, PRIMER (DEPENDING ON APPLICATION METHOD) REQUIRED WHERE INDICATED. SOPREMA SEALANT OR OWNER SPECIFIED SEALANT IS REQUIRED WHERE SEALANT IS INDICATED.

		310 QUADRAL DRIVE WADSWORTH, OHIO 44281 (330) 334-0066	
TITLE UNILAY SYSTEM @ CURB			
SCALE	DWN	CHK	APPROVAL DATE
NONE	DMT	PR	5/1/05
DRAWING NUMBER			REV
ULC-001			0

** USAGE OF THIS DRAWING IS GOVERNED BY THE TERMS OF SERVICE FOR SOPREMA DETAIL. PLEASE CONSULT THESE TERMS OF SERVICE PRIOR TO UTILIZING THIS DRAWING.